# DANSVILLE SCHOOLS NETWORK REFRESH PROJECT ITB –ADDENDUM 2
## Clarification of Specifications

---

This 2nd addendum is to provide clarification about the bid specifications. Aruba series switches are required as are the port set ups listed below. The specific model of Aruba switch is listed but not required. We are open to vendor recommendations for which model meets the brand and port requirements.

To accommodate this clarification, the bid opening date will also be pushed back 1 week from January 24, 2025 to January 31, 2025.

Previous Bid Opening Date:     01/24/2025 at 10:00 am
New Bid Opening Date:           01/31/2025 at 10:00 am

## Revised ITB Specifications

**Network Switches**
(7) Switches must be Aruba series, 48 Port PoE with 4 SFP56 Ports Supporting 10Gb each
    *Assume model 6300M but open to vendor recommendation
(3) Switches must be Aruba series, 24 Port PoE with SFP56 Ports Supporting 10Gb each
    *Assume model 6200F but open to vendor recommendation
(4) Switches must be Aruba series, 12 Port PoE with SFP56 Ports Supporting 10Gb each
    *Assume model 6100 but open to vendor recommendation
(5) Switches must be Aruba series, 48 Port PoE with SFP56 Ports Supporting 10Gb each
    *Assume model 6200F but open to vendor recommendation
All switches must deliver full PoE+ across all ports simultaneously

**Uninterruptable Power Supplies**

(9) Vertiv Liebert PS15 Lithium-Ion 3000VA with SNMP card 3U Short
Depth Rack-mounted Uninterruptable Power Supplies or equivalent